Project Documentation

Passivhaus Passivhaus Institut classic | plus | premium |

Abstract



ACF Passive House, Pine Plains, NY

Data of building			
Year of construction	2021		13.1
U-value external wall	0,116	Space heating	kWh/(m²a)
	$W/(m^2K)$		
U-value basement	0,143	Drives w. Energy Deneyable (DED)	57. I
	$W/(m^2K)$	Primary Energy Renewable (PER)	kWh/(m²a)
U-value roof	0,126	Conservation of various bla France	64.4
	$W/(m^2K)$	Generation of renewable Energy	kWh/(m²a)
U-value window	0,78	Non remarkle Drives v. Francy (DF)	0
	$W/(m^2K)$	Non-renewable Primary Energy (PE)	kWh/(m²a)
Heat recovery	79 %	Pressurization test n ₅₀	0.37ach50
Special features Thermal isolation of exterior covered spaces including Carport and Porch.			

Brief Description

ACF Passive House

This house provides accommodation for multi-generational family use. Set on a hillside commanding 270 degree views of farmland and adjacent valleys, the house accommodated ample common spaces and four bedroom suites.

The angled geometry of the house responds to the sweep of the south facing panoramic views, and allows for the differentiation of the central common spaces from the bent bedroom wings to the east and west.

A carport and two porches are integrated withing the primary roof form, but supported by clearly articulated (thermally isolated) steel support structures.

The construction is otherwise wood/stick framed, limiting the utilization of EPS foam to the basement subslab and wall insulation.

A north skylit stair is the vertical architectural element that unites the various components of the house.

Clad in copper, ipe and stone, the house utilizes durable and natural materials that will mature in appearance with the exposure and oxidation the design anticipates and welcomes.

Project Team:	
Architect	Barry Price, AIA www.barryprice.com
HVAC & Enclosure Consultant	Cramer Silkworth, Baukraft Engineering https://www.baukraft.com
Structural Engineer	Stinemire Engineering http://www.stinemireengineering.com
Passive House Certification	Certiphiers https://www.certiphiers.com
Contractor	Wolcott Builders http://www.wolcottbuilders.com
Certifying body:	
Passivhaus Institut Darmstadt www.passiv.de	
Certification ID	
6712	Project-ID (<u>www.passivehouse-database.org</u>)

Author of project documentation:				
Barry Price Architecture www.barryprice.com				
Date	Signature	į		
10.25.2021		[NW/	M	

I. Exterior Photos

from South







From East from Southeast



from North

I. Interior Photos



Looking South @ Interior



Stair




Kitchen


3. Section drawing:



4. Floor Plan: Main Level




4. Floor Plans cont: Upper (above) and Basement (below):




Page 6

5. Construction of the Foundation:




The foundation is entirely isolated from the ground with EPS foundation forms and exterior subgrade wall insulation.





6. Construction of the outer walls:






The wall construction consists of an interior Insulated service wall, wrapped with a vertical I-joist insulated buildout. The core structure accommodates and protects building services, remaining robustly insulated from exterior air.




Assembly no.	Building assembly description			Interior insulation?		
04ud	Above Grade	e Walls				
		Heat transmission resistance	[hr.ft².F/BTU]			
Orientation of building element	2-Wall	interior R _{si}	0.74			
Adjacent to	3-Ventilated	exterior R _{se} :	0.74			
Area section 1	R per inch	Area section 2 (optional)	R per inch	Area section 3 (optional)	R per inch	Thickness [in]
GWB	0.85					0.50
(air gap)						
Cellulose	3.70	Wood (softwood)*	1.11	Wood (softwood)*	1.11	5.50
Plywood	1.20					0.50
Cellulose	3.70	Wood (softwood)*	1.11	Wood (softwood)*	1.11	1.50
Cellulose	3.70	Cellulose	3.70	OSB	1.11	6.50
Cellulose	3.70	Wood (softwood)*	1.11	Wood (softwood)*	1.11	1.50
Perc	centage of sec. 1	Percent	age of sec. 2	Perc	entage of sec. 3	Total
	84%		13.3%		2.3%	16.00 in
U-value supplement		BTU/hr.ft².°F		R-valu	e: 49.9 hr.	ft ² .°F/BTU


7. Construction of the Roof:



The denspack insulated cavity Framed structure is capped with a structural overbuild to Provide for theremally isolated Overhangs and rakes.



8. Window and window installation:



9. Measurement of the airtight envelope:

The first pressure test was carried out by Baukraft Engineering after the airtight envelope had been completed on June 21, 2018.

The final pressure test was carried out by Baukraft Engineering after the finishes had been completed on June18, 2020.



Measurement	50 Pa pressure test air change n50 h-1
June 21, 2018	0.38
June18, 2020	0.38


Concept airtightness

Walls: interior sheetrock, taped and painted

Floor: concrete, 20mil vapor barrier Fenestration: airtight/watertight tapes

Roof: smart barrier membrane

10. Ventilation Unit:



Ventilation system manuf'r	Zehnder Novus 300
Heat Recovery efficiency	0.77 Unit η нк
Humidity Recovery efficiency	0.64

II. Ventilation Planning:

Supply air rooms are all main common rooms including living, dining, bedrooms, den and media room.

Exhaust air rooms are bathrooms, toilets and the kitchen.

12. Conditioning & Hot Water:



Description here:

13. Construction Costs:

Project costs have been withheld at the Owner's request.

15. PHPP Results:

